# Lock-Up Kit (Supply Only) **Specifications**



#### General

- 10 year structural guarantee
- All working architectural & structural drawings
- BCA compliant energy efficiency assessment
- Site classification (soil test)
- 2700mm high ceilings
- Delivery of all materials within 200km of Perth CBD

### **External**

- Prefabricated treated (minimum H2) pine wall frames (galvanised steel option also available)
- Treated pine roof trusses & ancillaries
- Treated pine verandah roof frame & ancillaries
- 90x90mm H3 treated pine verandah posts with galvanised steel stirrups (other options also available)
- R1.3 anticon reflective foil insulation to main roof
- Zincalume custom orb roof sheeting, gutters, downpipes & all required accessories (Colorbond option also available)
- Powder coated aluminium sliding doors & windows including flyscreens & key locks
- Double rebated jarrah external door frames
- Corinthian Urban range solid core external doors including weather seal
- Gainsborough external door furniture selection including deadbolt (keyed alike)
- Builders wrap reflective foil to external walls
- Hardieplank weatherboard external cladding (numerous alternate options also available)

## Raised treated Timber Stumped Floor System -Optional

- H5 treated floor stumps, 1m in height from natural ground level (galvanised steel floor stump option also available)
- Treated particle board flooring with fibre cement sheeting to wet areas
- Treated pine sub-floor floor system
- R2.5 high density under-floor insulation batts finished with 4.5mm hardieflex to enclose underside of sub-floor
- Two sets of external treated pine stairs with galvanised steel stirrups
- Treated pine balustrading & handrail
- H3 treated pine reeded decking (hardwood options also available)

### **Exclusions**

SEASONED

HOMES

PROFESSIONALS IN **BUILDING FRAMED** 

- All associated site works including compaction certificate
- Contour & feature survey
- Bushfire Attack Level assessment (if required)
- Local Shire planning & building fees
- All associated labour to erect home

Please note the Lock-Up Kit is designed and priced to be supplied only, constructed on a concrete slab or raised stumped floor system. Should you require any further information, please contact the office number below!